

Chipsmall Limited consists of a professional team with an average of over 10 year of expertise in the distribution of electronic components. Based in Hongkong, we have already established firm and mutual-benefit business relationships with customers from, Europe, America and south Asia, supplying obsolete and hard-to-find components to meet their specific needs.

With the principle of "Quality Parts, Customers Priority, Honest Operation, and Considerate Service", our business mainly focus on the distribution of electronic components. Line cards we deal with include Microchip, ALPS, ROHM, Xilinx, Pulse, ON, Everlight and Freescale. Main products comprise IC, Modules, Potentiometer, IC Socket, Relay, Connector. Our parts cover such applications as commercial, industrial, and automotives areas.

We are looking forward to setting up business relationship with you and hope to provide you with the best service and solution. Let us make a better world for our industry!



## Contact us

Tel: +86-755-8981 8866 Fax: +86-755-8427 6832

Email & Skype: info@chipsmall.com Web: www.chipsmall.com

Address: A1208, Overseas Decoration Building, #122 Zhenhua RD., Futian, Shenzhen, China







## INTEGRATED CIRCUITS

# DATA SHEET

# 74ABT2244

Octal buffer/line driver with  $30\Omega$  series termination resistors (3-State)

Product specification Supersedes data of 1996 Oct 23 IC23 Data Handbook





# Octal buffer/line driver with 30 $\Omega$ series termination resistors (3-State)

74ABT2244

#### **FEATURES**

- Octal bus interface
- 3-State buffers
- Live insertion/extraction permitted
- Outputs include series resistance of 30Ω, making external termination resistors unnecessary
- Output capability: +5mA/-32mA
- Latch-up protection exceeds 500mA per Jedec Std 17
- ESD protection exceeds 2000 V per MIL STD 883 Method 3015 and 200 V per Machine Model
- Power-up 3-State
- Same part as 74ABT244-1
- Inputs are disabled during 3-State mode

#### **DESCRIPTION**

The 74ABT2244 high-performance BiCMOS device combines low static and dynamic power dissipation with high speed.

The 74ABT2244 device is an octal buffer that is ideal for driving bus lines. The device features two Output Enables (1OE, 2OE), each controlling four of the 3-State outputs.

The 74ABT2244 is designed with  $30\Omega$  series resistance in both the High and Low states of the output. This design reduces line noise in applications such as memory address drivers, clock drivers and bus receivers/transmitters.

The 74ABT2244 is the same as the 74ABT244-1. The part number has been changed to reflect industry standards.


#### **QUICK REFERENCE DATA**

SYMBOL	PARAMETER	CONDITIONS T <sub>amb</sub> = 25°C; GND = 0V	TYPICAL	UNIT
<sup>†</sup> PLH <sup>†</sup> PHL	Propagation delay An to Yn	$C_L = 50pF; V_{CC} = 5V$	2.8 3.9	ns
C <sub>IN</sub>	Input capacitance	V <sub>I</sub> = 0V or V <sub>CC</sub>	4	pF
C <sub>OUT</sub>	Output capacitance	Outputs disabled; $V_O = 0V$ or $V_{CC}$	7	pF
I <sub>CCZ</sub>	Total supply current	Outputs disabled; V <sub>CC</sub> = 5.5V	50	μΑ

#### ORDERING INFORMATION

OTIDETHING IN OTHER				
PACKAGES	TEMPERATURE RANGE	OUTSIDE NORTH AMERICA	NORTH AMERICA	DWG NUMBER
20-Pin Plastic DIP	-40°C to +85°C	74ABT2244 N	74ABT2244 N	SOT146-1
20-Pin plastic SO	-40°C to +85°C	74ABT2244 D	74ABT2244 D	SOT163-1
20-Pin Plastic SSOP Type II	-40°C to +85°C	74ABT2244 DB	74ABT2244 DB	SOT339-1
20-Pin Plastic TSSOP Type I	-40°C to +85°C	74ABT2244 PW	7ABT2244PW DH	SOT360-1

#### **PIN CONFIGURATION**




#### **PIN DESCRIPTION**

PIN NUMBER	SYMBOL	NAME AND FUNCTION			
2, 4, 6, 8	1A0 – 1A3	Data inputs			
11, 13, 15, 17	2A0 – 2A3	Data inputs			
18, 16, 14, 12	1Y0 – 1Y3	Data outputs			
9, 7, 5, 3	2Y0 – 2Y3	Data outputs			
1, 19	1 <del>0E</del> , 2 <del>0E</del>	Output enables			
10	GND	Ground (0V)			
20	V <sub>CC</sub>	Positive supply voltage			


## Octal buffer/line driver with $30\Omega$ series termination resistors (3-State)

74ABT2244


#### **LOGIC SYMBOL**



### LOGIC SYMBOL (IEEE/IEC)



### SCHEMATIC OF EACH OUTPUT



#### **FUNCTION TABLE**

	INP	OUTPUTS			
1OE	1An	2 <del>OE</del>	1Yn	2Yn	
L	L	L	L	L	L
L	Н	L	Н	Н	Н
Н	Х	Н	Х	Z	Z

High voltage level

Low voltage level

X = Don't care Z = High impedance "off" state

# Octal buffer/line driver with $30\Omega$ series termination resistors (3-State)

74ABT2244

### **ABSOLUTE MAXIMUM RATINGS<sup>1, 2</sup>**

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V <sub>CC</sub>	DC supply voltage		-0.5 to +7.0	V
I <sub>IK</sub>	DC input diode current	V <sub>I</sub> < 0	-18	mA
VI	DC input voltage <sup>3</sup>		-1.2 to +7.0	V
l <sub>OK</sub>	DC output diode current	V <sub>O</sub> < 0	<b>–</b> 50	mA
V <sub>OUT</sub>	DC output voltage <sup>3</sup>	output in Off or High state	-0.5 to +5.5	V
I <sub>OUT</sub>	DC output current	output in Low state	128	mA
T <sub>stg</sub>	Storage temperature range		-65 to 150	°C

#### NOTES:

1. Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.

2. The performance capability of a high-performance integrated circuit in conjunction with its thermal environment can create junction temperatures which are detrimental to reliability. The maximum junction temperature of this integrated circuit should not exceed 150°C.

3. The input and output voltage ratings may be exceeded if the input and output current ratings are observed.

#### RECOMMENDED OPERATING CONDITIONS

CVMDOL	PARAMETER	LIM	LINUT	
SYMBOL	PARAMETER	Min	Max	UNIT
V <sub>CC</sub>	DC supply voltage	4.5	5.5	V
VI	Input voltage	0	V <sub>CC</sub>	V
V <sub>IH</sub>	High-level input voltage	2.0		V
V <sub>IL</sub>	Low-level Input voltage		0.8	V
I <sub>OH</sub>	High-level output current		-32	mA
I <sub>OL</sub>	Low-level output current		12	mA
Δt/Δν	Input transition rise or fall rate	0	5	ns/V
T <sub>amb</sub>	Operating free-air temperature range	-40	+85	°C

## Octal buffer/line driver with $30\Omega$ series termination resistors (3-State)

74ABT2244

#### DC ELECTRICAL CHARACTERISTICS

					LIMITS			
SYMBOL	PARAMETER	TEST CONDITIONS	Ta	<sub>mb</sub> = +25	5°C	T <sub>amb</sub> =	: –40°C 85°C	UNIT
			Min Typ Max Min		Min	Max	1	
V <sub>IK</sub>	Input clamp voltage $V_{CC} = 4.5V$ ; $I_{IK} = -18mA$				-1.2		-1.2	V
		$V_{CC} = 4.5V$ ; $I_{OH} = -3mA$ ; $V_I = V_{IL}$ or $V_{IH}$	2.5	2.9		2.5		V
V <sub>OH</sub>	High-level output voltage	$V_{CC} = 5.0V$ ; $I_{OH} = -3mA$ ; $V_I = V_{IL}$ or $V_{IH}$	3.0	3.4		3.0		V
		$V_{CC} = 4.5V$ ; $I_{OH} = -32mA$ ; $V_I = V_{IL}$ or $V_{IH}$	2.0	2.4		2.0		V
\/	Law layel autaut valtage	$V_{CC} = 4.5V$ ; $I_{OL} = 5mA$ ; $V_I = V_{IL}$ or $V_{IH}$		0.32	0.55		0.55	V
V <sub>OL</sub>	Low-level output voltage	$V_{CC} = 4.5V$ ; $I_{OL} = 12mA$ ; $V_I = V_{IL}$ or $V_{IH}$			0.8		0.8	V
II	Input leakage current	V <sub>CC</sub> = 5.5V; V <sub>I</sub> = GND or 5.5V		±0.01	±1.0		±1.0	μΑ
I <sub>OFF</sub>	Power-off leakage current	$V_{CC} = 0.0V$ ; $V_O$ or $V_I \le 4.5V$		5.0	100		100	μΑ
I <sub>PU/PD</sub>	Power-up/down 3-State output current <sup>3</sup>	$V_{\underline{CC}}$ = 2.1V; $V_{O}$ = 0.5V; $V_{I}$ = GND or $V_{CC}$ ; $V_{OE}$ = Don't care	o;		50		50	μА
I <sub>OZH</sub>	3-State output High current	$V_{CC} = 5.5V; V_O = 2.7V; V_I = V_{IL} \text{ or } V_{IH}$		0.1	50		50	μΑ
I <sub>OZL</sub>	3-State output Low current	$V_{CC} = 5.5V; V_O = 0.5V; V_I = V_{IL} \text{ or } V_{IH}$		-0.1	-50		-50	μΑ
I <sub>CEX</sub>	Output High leakage current	$V_{CC} = 5.5V$ ; $V_O = 5.5V$ ; $V_I = GND$ or $V_{CC}$		5.0	50		50	μΑ
I <sub>O</sub>	Output current <sup>1</sup>	V <sub>CC</sub> = 5.5V; V <sub>O</sub> = 2.5V	-50	-100	-180	-50	-180	mA
I <sub>CCH</sub>		$V_{CC} = 5.5V$ ; Outputs High, $V_I = GND$ or $V_{CC}$		50	250		250	μΑ
I <sub>CCL</sub>	Quiescent supply current	$V_{CC}$ = 5.5V; Outputs Low, $V_I$ = GND or $V_{CC}$		24	30		30	mA
I <sub>CCZ</sub>		$V_{CC}$ = 5.5V; Outputs 3-State; $V_{I}$ = GND or $V_{CC}$		50	250		250	μА
		Outputs enabled, one input at 3.4V, other inputs at $V_{CC}$ or GND; $V_{CC}$ = 5.5V		0.5	1.5		1.5	mA
Δl <sub>CC</sub>	Additional supply current per input pin <sup>2</sup>	Outputs 3-State, one enable input at 3.4V, other inputs at $V_{CC}$ or GND; $V_{CC}$ = 5.5V		50	250		250	μА
		Outputs 3-State, one enable input at 3.4V, other inputs at $V_{\rm CC}$ or GND; $V_{\rm CC}$ = 5.5V		0.5	1.5		1.5	mA

#### NOTES:

1. Not more than one output should be tested at a time, and the duration of the test should not exceed one second.

This is the increase in supply current for each input at 3.4V.
 This parameter is valid for any V<sub>CC</sub> between 0V and 2.1V, with a transition time of up to 10msec. From V<sub>CC</sub> = 2.1V to V<sub>CC</sub> = 5V ± 10% a transition time of up to 100µsec is permitted.

#### **AC CHARACTERISTICS**

GND = 0V;  $t_R$  =  $t_F$  = 2.5ns;  $C_L$  = 50pF,  $R_L$  = 500 $\Omega$ 


SYMBOL PARAMETER		WAVEFORM	T <sub>e</sub>	<sub>amb</sub> = +25° CC = +5.0	°C V	T <sub>amb</sub> = -40° V <sub>CC</sub> = +5.	UNIT	
			Min	Тур	Max	Min	Max	
t <sub>PLH</sub> t <sub>PHL</sub>	Propagation delay An to Yn	1	1.0 1.0	2.8 3.9	4.3 5.3	1.0 1.0	4.7 5.6	ns
t <sub>PZH</sub> t <sub>PZL</sub>	Output enable time to High and Low level	2	1.1 2.1	3.3 5.0	4.8 7.3	1.1 2.1	5.5 8.3	ns
t <sub>PHZ</sub>	Output disable time from High and Low level	2	2.1 1.7	3.7 3.4	5.6 5.3	2.1 1.7	6.6 5.8	ns

# Octal buffer/line driver with $30\Omega$ series termination resistors (3-State)


74ABT2244

#### **AC WAVEFORMS**

 $V_{M} = 1.5V, V_{IN} = GND \text{ to } 3.0V$ 




Waveform 1. Waveforms Showing the Input (An) to Output (Yn)
Propagation Delays



Waveform 2. Waveforms Showing the 3-State Output Enable and Disable Times


### **TEST CIRCUIT AND WAVEFORMS**



74ABT2244

### DIP20: plastic dual in-line package; 20 leads (300 mil)

SOT146-1



### DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub> min.	A <sub>2</sub> max.	b	b <sub>1</sub>	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	e <sub>1</sub>	L	ME	Мн	w	Z <sup>(1)</sup> max.
mm	4.2	0.51	3.2	1.73 1.30	0.53 0.38	0.36 0.23	26.92 26.54	6.40 6.22	2.54	7.62	3.60 3.05	8.25 7.80	10.0 8.3	0.254	2.0
inches	0.17	0.020	0.13	0.068 0.051	0.021 0.015	0.014 0.009	1.060 1.045	0.25 0.24	0.10	0.30	0.14 0.12	0.32 0.31	0.39 0.33	0.01	0.078

#### Note

1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.


OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUE DATE
SOT146-1			SC603		<del>92-11-17</del> 95-05-24

1998 Jan 16 7

74ABT2244

### SO20: plastic small outline package; 20 leads; body width 7.5 mm

SOT163-1



#### DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	O	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	٧	w	у	z <sup>(1)</sup>	θ
mm	2.65	0.30 0.10	2.45 2.25	0.25	0.49 0.36	0.32 0.23	13.0 12.6	7.6 7.4	1.27	10.65 10.00	1.4	1.1 0.4	1.1 1.0	0.25	0.25	0.1	0.9 0.4	8°
inches	0.10	0.012 0.004	0.096 0.089	0.01	0.019 0.014	0.013 0.009	0.51 0.49	0.30 0.29	0.050	0.42 0.39	0.055	0.043 0.016	0.043 0.039	0.01	0.01	0.004	0.035 0.016	o°

#### Note


1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.

OUTLINE		REFER	RENCES		EUROPEAN	ISSUE DATE	
VERSION	IEC	JEDEC	EDEC EIAJ		PROJECTION	ISSUE DATE	
SOT163-1	075E04	MS-013AC				<del>92-11-17</del> 95-01-24	

74ABT2244

### SSOP20: plastic shrink small outline package; 20 leads; body width 5.3 mm

SOT339-1



#### DIMENSIONS (mm are the original dimensions)

UNIT	A max.	Α1	A <sub>2</sub>	А3	р <sub>р</sub>	O	D <sup>(1)</sup>	E <sup>(1)</sup>	Ф	HE	L	Lp	œ	٧	v	у	Z <sup>(1)</sup>	θ
mm	2.0	0.21 0.05	1.80 1.65	0.25	0.38 0.25	0.20 0.09	7.4 7.0	5.4 5.2	0.65	7.9 7.6	1.25	1.03 0.63	0.9 0.7	0.2	0.13	0.1	0.9 0.5	8° 0°

#### Note

1. Plastic or metal protrusions of 0.20 mm maximum per side are not included.


OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUE DATE
SOT339-1		MO-150AE			<del>93-09-08</del> 95-02-04


1998 Jan 16 9

74ABT2244

### TSSOP20: plastic thin shrink small outline package; 20 leads; body width 4.4 mm

SOT360-1





#### DIMENSIONS (mm are the original dimensions)

UNIT	A max.	Α1	A <sub>2</sub>	A <sub>3</sub>	рb	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	1.10	0.15 0.05	0.95 0.80	0.25	0.30 0.19	0.2 0.1	6.6 6.4	4.5 4.3	0.65	6.6 6.2	1.0	0.75 0.50	0.4 0.3	0.2	0.13	0.1	0.5 0.2	8° 0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	RENCES	EUROPEAN	ISSUE DATE
VERSION	IEC	JEDEC	EIAJ	PROJECTION	ISSUEDATE
SOT360-1		MO-153AC			<del>-93-06-16-</del> 95-02-04

1998 Jan 16 10

Octal buffer/line driver with  $30\Omega$  series termination resistors (3-State)

74ABT2244

**NOTES** 

# Octal buffer/line driver with $30\Omega$ series termination resistors (3-State)

74ABT2244

#### Data sheet status

Data sheet status	Product status	Definition [1]
Objective specification	Development	This data sheet contains the design target or goal specifications for product development. Specification may change in any manner without notice.
Preliminary specification	Qualification	This data sheet contains preliminary data, and supplementary data will be published at a later date. Philips Semiconductors reserves the right to make chages at any time without notice in order to improve design and supply the best possible product.
Product specification	Production	This data sheet contains final specifications. Philips Semiconductors reserves the right to make changes at any time without notice in order to improve design and supply the best possible product.

<sup>[1]</sup> Please consult the most recently issued datasheet before initiating or completing a design.

#### Definitions

**Short-form specification** — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

#### **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

**Right to make changes** — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

Philips Semiconductors 811 East Arques Avenue P.O. Box 3409 Sunnyvale, California 94088–3409 Telephone 800-234-7381 © Copyright Philips Electronics North America Corporation 1998 All rights reserved. Printed in U.S.A.

print code Date of release: 05-96

Document order number: 9397-750-03466

Let's make things better.

Philips Semiconductors



