

Chipsmall Limited consists of a professional team with an average of over 10 year of expertise in the distribution of electronic components. Based in Hongkong, we have already established firm and mutual-benefit business relationships with customers from, Europe, America and south Asia, supplying obsolete and hard-to-find components to meet their specific needs.

With the principle of "Quality Parts, Customers Priority, Honest Operation, and Considerate Service", our business mainly focus on the distribution of electronic components. Line cards we deal with include Microchip, ALPS, ROHM, Xilinx, Pulse, ON, Everlight and Freescale. Main products comprise IC, Modules, Potentiometer, IC Socket, Relay, Connector. Our parts cover such applications as commercial, industrial, and automotives areas.

We are looking forward to setting up business relationship with you and hope to provide you with the best service and solution. Let us make a better world for our industry!



### Contact us

Tel: +86-755-8981 8866 Fax: +86-755-8427 6832

Email & Skype: info@chipsmall.com Web: www.chipsmall.com

Address: A1208, Overseas Decoration Building, #122 Zhenhua RD., Futian, Shenzhen, China







#### INTEGRATED CIRCUITS

# DATA SHEET

### **CBTS3257**

Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

Product data 2002 Sep 27





### Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

#### **FEATURES**

- 5  $\Omega$  switch connection between two ports
- TTL-compatible input levels
- Schottky diodes on I/O clamp undershoot
- Minimal propagation delay through the switch
- Latch-up protection exceeds 500 mA per JESD78
- ESD protection exceeds 2000 V HBM per JESD22-A114,
   200 V MM per JESD22-A115 and 1000 V CDM per JESD22-C101

#### **DESCRIPTION**


The CBTS3257 is a quad 1-of-2 high-speed TTL-compatible multiplexer/demultiplexer. The low on resistance of the switch allows inputs to be connected to outputs without adding propagation delay or generating additional ground bounce noise.

Output Enable  $(\overline{OE})$  and select-control (S) inputs select the appropriate B1 and B2 outputs for the A-input data.

Internal Schottky diode provides I/O undershoot protection.

The CBTS3257 is characterized for operation from -40 to +85 °C.

#### PIN CONFIGURATION



#### **PIN DESCRIPTION**

PIN NUMBER	SYMBOL	NAME AND FUNCTION					
1	S	Select-control input					
2, 3, 5, 6, 10, 11, 13, 14	1B1, 1B2, 2B1, 2B2 3B1, 3B2 4B1, 4B2	B outputs					
4, 7, 9, 12	1A, 2A, 3A, 4A	A inputs					
8	GND	Ground (0 V)					
15	ŌĒ	Output enable					
16	V <sub>CC</sub>	Positive supply voltage					

#### **ORDERING INFORMATION**


PACKAGES	TEMPERATURE RANGE	ORDER CODE	TOPSIDE MARK	DWG NUMBER
16-pin plastic SO	−40 to 85 °C	CBTS3257D	CBTS3257D	SOT109-1
16-pin plastic SSOP	−40 to 85 °C	CBTS3257DB	CS3257	SOT338-1
16-pin plastic SSOP (QSOP)	–40 to 85 °C	CBTS3257DS	CBS3257	SOT519-1
16-pin plastic TSSOP	-40 to 85 °C	CBTS3257PW	CBS3257	SOT403-1

Standard packing quantities and other packaging data is available at www.philipslogic.com/packaging.

# Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

### **LOGIC DIAGRAM (positive logic)**



#### **FUNCTION TABLE**

INP	JTS	FUNCTION
ŌĒ	S	FONCTION
L	L	A port = B1 port
L	Н	A port = B2 port
Н	Χ	Disconnect

### Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

#### ABSOLUTE MAXIMUM RATINGS<sup>1</sup>

SYMBOL	PARAMETER	CONDITIONS	RATING	UNIT
V <sub>CC</sub>	DC supply voltage		-0.5 to +7.0	V
V <sub>I</sub>	DC input voltage <sup>2</sup>		-0.5 to +7.0	V
	Continuous channel current		128	mA
I <sub>K</sub>	Input clamp current	V <sub>I/O</sub> < 0	<del>-</del> 50	mA
T <sub>stg</sub>	Storage temperature range		-65 to +150	°C

#### NOTES:

#### RECOMMENDED OPERATING CONDITIONS

SYMBOL	PARAMETER	LIM	UNIT	
STWIBUL	PARAMETER	MIN	MAX	UNII
V <sub>CC</sub>	DC supply voltage	4.5	5.5	V
V <sub>IH</sub>	High-level input voltage	2.0	_	V
V <sub>IL</sub>	Low-level Input voltage	_	0.8	V
T <sub>amb</sub>	Operating free-air temperature range	-40	+85	°C

#### NOTE:

#### DC ELECTRICAL CHARACTERISTICS

						LIMITS		
SYMBOL	PARAM	ETER		TEST CONDITIONS	T <sub>amb</sub>	UNIT		
		_			MIN	TYP <sup>1</sup>	MAX	
V	Input clamp voltage	A or B in	puts	$V_{CC} = 4.5 \text{ V; } I_1 = -18 \text{ mA}$	_	_	-0.8	V
V <sub>IK</sub>	input clamp voltage	Control i	nputs	V <sub>CC</sub> = 4.5 V, I <sub>1</sub> = -16 IIIA	_	_	-1.2	V
$V_{P}$	Pass voltage			$V_I = V_{CC} = 5.0 \text{ V}; I/O = -100 \text{ mA}$	3.4	3.6	3.9	V
lı	Input leakage current			$V_{CC} = 5.5 \text{ V}; V_I = \text{GND or } 5.5 \text{ V}$	_	_	±1	μΑ
I <sub>CC</sub>	Quiescent supply curr	ent		$V_{CC} = 5.5 \text{ V}; I_O = 0, V_I = V_{CC} \text{ or GND}$	_	_	3	μΑ
Δl <sub>CC</sub>	Additional supply curre	ent per inp	out pin <sup>2</sup>	$V_{CC}$ = 5.5 V, one input at 3.4 V, other inputs at $V_{CC}$ or GND	_	_	2.5	mA
C <sub>I</sub>	Control pins capacitar	nce		V <sub>I</sub> = 3 V or 0	_	3.3	_	pF
C	Off conscitones		A port	$V_O = 3 \text{ V or } 0; \overline{OE} = V_{CC}$	_	9.9	_	pF
C <sub>IO(OFF)</sub>	Off capacitance		B port	$V_O = 3 \text{ V or } 0; \overline{OE} = V_{CC}$	_	6.4	_	pF
				V <sub>CC</sub> = 4.5 V; V <sub>I</sub> = 0V; I <sub>I</sub> = 64 mA		5	7	Ω
r <sub>on</sub> 3	On-resistance			$V_{CC} = 4.5 \text{ V}; V_I = 0 \text{V}; I_I = 30 \text{ mA}$		5	7	Ω
				$V_{CC} = 4.5 \text{ V}; V_{I} = 2.4 \text{ V}; I_{I} = 15 \text{ mA}$	_	10	15	Ω

- All typical values are at V<sub>CC</sub> = 5 V, T<sub>amb</sub> = 25 °C.
   This is the increase in supply current for each input that is at the specified TTL voltage level rather than V<sub>CC</sub> or GND
   Measured by the voltage drop between the A and the B terminals at the indicated current through the switch. On-state resistance is determined by the lowest voltage of the two (A or B) terminals.

<sup>1.</sup> Stresses beyond those listed may cause permanent damage to the device. These are stress ratings only and functional operation of the device at these or any other conditions beyond those indicated under "recommended operating conditions" is not implied. Exposure to absolute-maximum-rated conditions for extended periods may affect device reliability.

<sup>2.</sup> The input and output negative-voltage ratings may be exceeded if the input and output clamp-current ratings are observed.

<sup>1.</sup> All unused control inputs of the device must be held at  $V_{CC}$  or GND to ensure proper device operation.

## Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

#### **AC CHARACTERISTICS**


 $T_{amb} = -40 \text{ to } +85 \,^{\circ}\text{C}; \, C_L = 50 \text{ pF}$ 

				LIM	ITS	
SYMBOL	PARAMETER	FROM (INPUT)	TO (OUTPUT)	$V_{CC} = +5.0$	UNIT	
			(001101)	MIN	MAX	
t <sub>pd</sub>	Propagation delay <sup>1</sup>	A or B	B or A		0.25	ns
t <sub>pd</sub>	Propagation delay	S	Α	1.6	5.0	ns
	Output enable time	ŌĒ	A or B	1.8	5.1	ns
t <sub>en</sub>	to High and Low level	S	В	1.6	5.2	ns
+	Output disable time	ŌĒ	A or B	2.2	5.5	ns
t <sub>dis</sub>	from High and Low level	S	В	1.0	5.0	ns


#### NOTE:

#### **AC WAVEFORMS**

 $V_{M} = 1.5 \text{ V}, V_{IN} = \text{GND to } 3.0 \text{ V}$ 




**Waveform 1. Input to Output Propagation Delays** 



### Waveform 2. 3-State Output Enable and Disable Times NOTES:

- 1.  $t_{PLZ}$  and  $t_{PHZ}$  are the same as  $t_{dis}$ .
- 2. t<sub>PZL</sub> and t<sub>PZH</sub> are the same as t<sub>en</sub>.
- 3.  $t_{PLH}$  and  $t_{PHL}$  are the same as  $t_{pd}$ .

#### **TEST CIRCUIT AND WAVEFORMS**




#### NOTES:

- 1. All input pulses are supplied by generators having the following characteristics: PRR  $\leq$  10 MHz,  $Z_O=50~\Omega,~t_f\leq 2.5~ns,~t_f\leq 2.5~ns.$
- The outputs are measured one at a time with one transition per measurement.

<sup>1.</sup> The propagation delay is the calculated RC time constant of the typical on-state resistance of the switch and the specified load capacitance, when driven by an ideal voltage source (zero output impedance).

#### SO16: plastic small outline package; 16 leads; body width 3.9 mm

SOT109-1



#### DIMENSIONS (inch dimensions are derived from the original mm dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	А3	bp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	1.75	0.25 0.10	1.45 1.25	0.25	0.49 0.36	0.25 0.19	10.0 9.8	4.0 3.8	1.27	6.2 5.8	1.05	1.0 0.4	0.7 0.6	0.25	0.25	0.1	0.7 0.3	8°
inches	0.069	0.010 0.004	0.057 0.049	0.01		0.0100 0.0075		0.16 0.15	0.050	0.244 0.228	0.041	0.039 0.016	0.028 0.020	0.01	0.01	0.004	0.028 0.012	0°

#### Note


1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	EIAJ		PROJECTION	1330E DATE
SOT109-1	076E07	MS-012				<del>97-05-22</del> 99-12-27

**CBTS3257** 

SSOP16: plastic shrink small outline package; 16 leads; body width 5.3 mm

SOT338-1



#### DIMENSIONS (mm are the original dimensions)

UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	С	D <sup>(1)</sup>	E <sup>(1)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
mm	2.0	0.21 0.05	1.80 1.65	0.25	0.38 0.25	0.20 0.09	6.4 6.0	5.4 5.2	0.65	7.9 7.6	1.25	1.03 0.63	0.9 0.7	0.2	0.13	0.1	1.00 0.55	8° 0°

#### Note

1. Plastic or metal protrusions of 0.25 mm maximum per side are not included.


OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE
SOT338-1		MO-150				<del>-95-02-04</del> 99-12-27

# Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

SSOP16: plastic shrink small outline package; 16 leads; body width 3.9 mm; lead pitch 0.635 mm

SOT519-1



UNIT	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bp	С	D (1)	E <sup>(1)</sup>	е	HE	L	Lp	v	w	у	Z <sup>(1)</sup>	θ
mm	1.73	0.25 0.10	1.55 1.40	0.25	0.31 0.20	0.25 0.18	5.0 4.8	4.0 3.8	0.635	6.2 5.8	1.0	0.89 0.41	0.2	0.18	0.09	0.18 0.05	8° 0°

#### Note


1. Plastic or metal protrusions of 0.20 mm maximum per side are not included.


OUTLINE					EUROPEAN	ISSUE DATE	
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE	
SOT519-1						99-05-04	


**CBTS3257** 


TSSOP16: plastic thin shrink small outline package; 16 leads; body width 4.4 mm

SOT403-1









#### DIMENSIONS (mm are the original dimensions)

UI	III	A max.	A <sub>1</sub>	A <sub>2</sub>	A <sub>3</sub>	bр	С	D <sup>(1)</sup>	E <sup>(2)</sup>	е	HE	L	Lp	Q	v	w	у	Z <sup>(1)</sup>	θ
m	m	1.10	0.15 0.05	0.95 0.80	0.25	0.30 0.19	0.2 0.1	5.1 4.9	4.5 4.3	0.65	6.6 6.2	1.0	0.75 0.50	0.4 0.3	0.2	0.13	0.1	0.40 0.06	8° 0°

#### Notes

- 1. Plastic or metal protrusions of 0.15 mm maximum per side are not included.
- 2. Plastic interlead protrusions of 0.25 mm maximum per side are not included.

OUTLINE		REFER	EUROPEAN	ISSUE DATE		
VERSION	IEC	JEDEC	EIAJ		PROJECTION	ISSUE DATE
SOT403-1		MO-153				<del>-95-04-04</del> 99-12-27

# Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

CBTS3257

#### **REVISION HISTORY**

ĺ	Rev	Date	Description			
Ĭ	_1	2002 Sep 27	Product data (9397 750 10333); initial version			
			Engineering Change Notice: 853–2380 28892 (2002 Sep 10)			

### Quad 1-of-2 multiplexer/demultiplexer with Schottky diode

**CBTS3257** 

#### Data sheet status

Data sheet status <sup>[1]</sup>	Product status <sup>[2]</sup>	Definitions
Objective data	Development	This data sheet contains data from the objective specification for product development. Philips Semiconductors reserves the right to change the specification in any manner without notice.
Preliminary data	Qualification	This data sheet contains data from the preliminary specification. Supplementary data will be published at a later date. Philips Semiconductors reserves the right to change the specification without notice, in order to improve the design and supply the best possible product.
Product data	Production	This data sheet contains data from the product specification. Philips Semiconductors reserves the right to make changes at any time in order to improve the design, manufacturing and supply. Changes will be communicated according to the Customer Product/Process Change Notification (CPCN) procedure SNW-SQ-650A.

<sup>[1]</sup> Please consult the most recently issued data sheet before initiating or completing a design.

#### **Definitions**

Short-form specification — The data in a short-form specification is extracted from a full data sheet with the same type number and title. For detailed information see the relevant data sheet or data handbook.

Limiting values definition — Limiting values given are in accordance with the Absolute Maximum Rating System (IEC 60134). Stress above one or more of the limiting values may cause permanent damage to the device. These are stress ratings only and operation of the device at these or at any other conditions above those given in the Characteristics sections of the specification is not implied. Exposure to limiting values for extended periods may affect device reliability.

**Application information** — Applications that are described herein for any of these products are for illustrative purposes only. Philips Semiconductors make no representation or warranty that such applications will be suitable for the specified use without further testing or modification.

#### **Disclaimers**

**Life support** — These products are not designed for use in life support appliances, devices or systems where malfunction of these products can reasonably be expected to result in personal injury. Philips Semiconductors customers using or selling these products for use in such applications do so at their own risk and agree to fully indemnify Philips Semiconductors for any damages resulting from such application.

Right to make changes — Philips Semiconductors reserves the right to make changes, without notice, in the products, including circuits, standard cells, and/or software, described or contained herein in order to improve design and/or performance. Philips Semiconductors assumes no responsibility or liability for the use of any of these products, conveys no license or title under any patent, copyright, or mask work right to these products, and makes no representations or warranties that these products are free from patent, copyright, or mask work right infringement, unless otherwise specified.

#### **Contact information**

For additional information please visit

http://www.semiconductors.philips.com. Fax: +31 40 27 24825

For sales offices addresses send e-mail to: sales.addresses@www.semiconductors.philips.com.

© Koninklijke Philips Electronics N.V. 2002 All rights reserved. Printed in U.S.A.

Date of release: 09-02

Document order number: 9397 750 10333

Let's make things better.

Philips Semiconductors





<sup>[2]</sup> The product status of the device(s) described in this data sheet may have changed since this data sheet was published. The latest information is available on the Internet at URL http://www.semiconductors.philips.com.