

Chipsmall Limited consists of a professional team with an average of over 10 year of expertise in the distribution of electronic components. Based in Hongkong, we have already established firm and mutual-benefit business relationships with customers from, Europe, America and south Asia, supplying obsolete and hard-to-find components to meet their specific needs.

With the principle of "Quality Parts, Customers Priority, Honest Operation, and Considerate Service", our business mainly focus on the distribution of electronic components. Line cards we deal with include Microchip, ALPS, ROHM, Xilinx, Pulse, ON, Everlight and Freescale. Main products comprise IC, Modules, Potentiometer, IC Socket, Relay, Connector. Our parts cover such applications as commercial, industrial, and automotives areas.

We are looking forward to setting up business relationship with you and hope to provide you with the best service and solution. Let us make a better world for our industry!



# Contact us

Tel: +86-755-8981 8866 Fax: +86-755-8427 6832

Email & Skype: info@chipsmall.com Web: www.chipsmall.com

Address: A1208, Overseas Decoration Building, #122 Zhenhua RD., Futian, Shenzhen, China









# PC8110xNSZ Series

# DIP 4pin High Speed under High Load Resistance Photocoupler



#### **■** Description

**PC8110xNSZ Series** contains an IRED optically coupled to a phototransistor built-in schottky barrier diode.

It is packaged in a 4-pin DIP, and SMT gullwing lead-form option.

Input-output isolation voltage(rms) is 5.0kV. CTR is 50% to 400% at input current of 5mA.

#### ■ Features

- 1. 4pin DIP package
- Double transfer mold package (Ideal for Flow Soldering)
- 3. High speed response at turn-off time due to built-in schottky barrier diode (at saturation mode)
- 4. High isolation voltage between input and output (V<sub>iso(rms)</sub>: 5kV)

#### ■ Agency approvals/Compliance

- Recognized by UL1577 (Double protection isolation), file No. E64380 (as model No. PC8110)
- 2. Package resin: UL flammability grade (94V-0)

#### ■ Applications

1. Home appliances




#### ■ Internal Connection Diagram

# Schottky barrier diode 1 Anode 3 Cathode 2 Emitter 5 Collector

#### **■** Outline Dimensions

(Unit: mm)



Product mass: approx. 0.21g



#### Date code (2 digit)

	1st o	digit		2nd digit		
	Year of p	roduction		Month of production		
A.D.	Mark	A.D	Mark	Month	Mark	
1990	A	2002	P	January	1	
1991	В	2003	R	February	2	
1992	С	2004	S	March	3	
1993	D	2005	T	April	4	
1994	Е	2006	U	May	5	
1995	F	2007	V	June	6	
1996	Н	2008	W	July	7	
1997	J	2009	X	August	8	
1998	K	2010	A	September	9	
1999	L	2011	В	October	0	
2000	M	2012	С	November	N	
2001	N	:	:	December	D	

repeats in a 20 year cycle

### Factory identification mark

Factory identification Mark	Country of origin	
no mark	Japan	
	Indonesia	
$\overline{\hspace{1cm}}$	Philippines	
	China	

<sup>\*</sup> This factory marking is for identification purpose only.

Please contact the local SHARP sales representative to see the actural status of the production.

Rank mark

Refer to the Model Line-up table



■ Absolute Maximum Ratings

■ Absolute Maximum Ratings $(T_a=25^{\circ}C)$						
	Parameter	Symbol	Rating	Unit		
	Forward current	$I_{\mathrm{F}}$	50	mA		
Input	*1 Peak forward current	$I_{FM}$	1.0	A		
InI	Reverse voltage	$V_R$	6	V		
	Power dissipation	P	70	mW		
	Collector-emitter voltage	$V_{CEO}$	70	V		
Output	Emitter-collector voltage	$V_{ECO}$	0.1	V		
Out	Collector current	$I_C$	30	mA		
	Collector power dissipation	$P_{C}$	150	mW		
Total power dissipation		$P_{tot}$	200	mW		
*2 I	solation voltage	V <sub>iso (rms)</sub>	5.0	kV		
(	Operating temperature	$T_{opr}$	-30 to +100	°C		
	Storage temperature	$T_{stg}$	-55 to +125	°C		
*3 €	Soldering temperature	$T_{sol}$	260	°C		

<sup>\*1</sup> Pulse width≤100µs, Duty ratio: 0.001 \*2 40 to 60%RH, AC for 1 minute, f=60Hz

## **■** Electro-optical Characteristics

 $(T_a=25^{\circ}C)$ 

		•							$(1_{a}-25)$
		Parameter		Symbol	Conditions	MIN.	TYP.	MAX.	Unit
	Forward voltage		$V_F$	I <sub>F</sub> =20mA	_	1.2	1.4	V	
T.,4	Input	Peak forward voltage		$V_{FM}$	I <sub>FM</sub> =0.5A	_	-	3.0	V
Input		Reverse Current		$I_R$	$V_R=4V$	_	-	10	μΑ
	7	Terminal capacitance		Ct	V=0, f=1kHz	_	30	250	pF
0-44	(	Collector darl	current	$I_{CEO}$	$V_{CE}=50V, I_{F}=0$	_	-	100	nA
Output	*4 (	Collector-emitter brea	akdown voltage	BV <sub>CEO</sub>	$I_{C}=0.1 \text{mA}, I_{F}=0$	70	-	_	V
		Collector current		$I_{C}$	$I_F=5mA, V_{CE}=5V$	2.5	-	20	mA
	(	Collector-emitter saturation voltage		V <sub>CE (sat)</sub>	$I_F=20\text{mA}, I_C=1\text{mA}$	_	0.15	0.35	V
	I	Isolation resistance		R <sub>ISO</sub>	DC500V, 40 to 60%RH	5×10 <sup>10</sup>	1011	_	Ω
	F	Floating capa	citance	$C_{\mathrm{f}}$	V=0, f=1MHz	_	0.6	1.0	pF
		Not saturated	Rise time	t <sub>r</sub>	$V_{CE}$ =2V, $I_C$ =2mA, $R_L$ =100 $\Omega$	_	3	20	
Transfer			Fall time	$t_{\mathrm{f}}$		_	2	10	
charac- teristics	me	Saturated 1	Turn-on time	t <sub>on</sub>	$V_{CC}$ =5V, $I_C$ =20mA, $R_L$ =10k $\Omega$	_	2	13	
teristics	se ti		Storage time	$t_{\rm s}$		_	9	50	
	bou		Turn-off time	$t_{\rm off}$		_	23	90	μs
	Res	Saturated 2	Turn-on time	t <sub>on</sub>	$V_{CC}$ =5V, $I_{C}$ =20mA, $R_{L}$ =100k $\Omega$	_	3	13	
			Storage time	t <sub>s</sub>		_	10	50	
			Turn-off time	$t_{\rm off}$		_	27	100	

<sup>\*4</sup> The collector-emitter voltage has negative resistance characteristics since this device has built-in base-emitter resistor. Therefore, please be careful not to provide the voltage that goes beyond absolute maximum ratings.

<sup>\*3</sup> For 10s



#### **■** Model Line-up

Lead Form	Through-Hole	SMT G	ullwing	Rank mark	I <sub>C</sub> [mA]
Package	100pcs/sleeve	100pcs/sleeve	2000pcs/reel	Kalik illalk	$(I_F=5mA, V_{CE}=5V, T_a=25^{\circ}C)$
•	PC81100NSZ	PC81100NIZ	PC81100NIP	with or without	2.5 to 20.0
	PC81101NSZ	PC81101NIZ	PC81101NIP	A	3.0 to 6.0
	PC81102NSZ	PC81102NIZ	PC81102NIP	В	5.0 to 10.0
Model No.	PC81103NSZ	PC81103NIZ	PC81103NIP	С	7.5 to 15.0
	PC81105NSZ	PC81105NIZ	PC81105NIP	A or B	3.0 to 10.0
	PC81106NSZ	PC81106NIZ	PC81106NIP	B or C	5.0 to 15.0
	PC81108NSZ	PC81108NIZ	PC81108NIP	A, B or C	3.0 to 15.0

Please contact a local SHARP sales representative to inquire about production status and Lead-Free options.



Fig.1 Forward Current vs. Ambient Temperature




Fig.3 Collector Power Dissipation vs. Ambient Temperature




Fig.5 Peak Forward Current vs. Duty Ratio




Fig.2 Diode Power Dissipation vs.
Ambient Temperature




Fig.4 Total Power Dissipation vs. Ambient Temperature




Fig.6 Forward Current vs. Forward Voltage






Fig.7 Current Transfer Ratio vs. Forward Current




Fig.9 Relative Current Transfer Ratio vs. Ambient Temperature




Fig.11 Collector Dark Current vs. Ambient Temperature




Fig.8 Collector Current vs. Collector-emitter Voltage




Fig.10 Collector - emitter Saturation Voltage vs. Ambient Temperature




Fig.12 Response Time vs. Load Resistance (saturation region)






Fig.13 Response Time vs. Load Resistance (active region)





Fig.14 Test Circuit for Response Time



Please refer to the conditions in Fig.12 and Fig.13

Fig.15 Frequency Response





Fig.16 Collector-emitter Saturation Voltage vs. Forward Current



Remarks: Please be aware that all data in the graph are just for reference and not for guarantee.



#### ■ Design Considerations

#### Design guide

While operating at I<sub>F</sub><5.0mA, CTR variation may increase.

Please make design considering this fact.

This product is not designed against irradiation and incorporates non-coherent IRED.

The collector-emitter voltage has negative resistance characteristics since this device has built-in base-emitter resistor.


Therefore, please be careful not to provide the voltage that goes beyond absolute maximum ratings.

#### Degradation

In general, the emission of the IRED used in photocouplers will degrade over time.

In the case of long term operation, please take the general IRED degradation (50% degradation over 5years) into the design consideration.

#### Recommended Foot Print (reference)



(Unit: mm)

<sup>☆</sup> For additional design assistance, please review our corresponding Optoelectronic Application Notes.



#### ■ Manufacturing Guidelines


#### Soldering Method

#### Reflow Soldering:

Reflow soldering should follow the temperature profile shown below.

Soldering should not exceed the curve of temperature profile and time.

Please don't solder more than twice.



#### Flow Soldering:

Due to SHARP's double transfer mold construction submersion in flow solder bath is allowed under the below listed guidelines.

Flow soldering should be completed below 270°C and within 10s.

Preheating is within the bounds of 100 to 150°C and 30 to 80s.

Please don't solder more than twice.

#### Hand soldering

Hand soldering should be completed within 3s when the point of solder iron is below 400°C.

Please don't solder more than twice.

#### Other notices

Please test the soldering method in actual condition and make sure the soldering works fine, since the impact on the junction between the device and PCB varies depending on the tooling and soldering conditions.



#### Cleaning instructions

#### Solvent cleaning:

Solvent temperature should be 45°C or below Immersion time should be 3minutes or less

#### Ultrasonic cleaning:

The impact on the device varies depending on the size of the cleaning bath, ultrasonic output, cleaning time, size of PCB and mounting method of the device.

Therefore, please make sure the device withstands the ultrasonic cleaning in actual conditions in advance of mass production.

#### Recommended solvent materials:

Ethyl alcohol, Methyl alcohol and Isopropyl alcohol

In case the other type of solvent materials are intended to be used, please make sure they work fine in actual using conditions since some materials may erode the packaging resin.

#### Presence of ODC

This product shall not contain the following materials.

And they are not used in the production process for this device.

Regulation substances:CFCs, Halon, Carbon tetrachloride, 1.1.1-Trichloroethane (Methylchloroform)

Specific brominated flame retardants such as the PBBOs and PBBs are not used in this product at all.

Sheet No.: D2-A03801EN



#### ■ Package specification

#### Sleeve package

Package materials

Sleeve: HIPS (with anti-static material)

Stopper: Styrene-Elastomer


#### Package method


MAX. 100pcs of products shall be packaged in a sleeve. Both ends shall be closed by tabbed and tabless stoppers.

The product shall be arranged in the sleeve with its anode mark on the tabless stopper side.

MAX. 20 sleeves in one case.

#### Sleeve outline dimensions







#### ● Tape and Reel package


Package materials

Carrier tape: PS

Cover tape : PET (three layer system)


Reel: PS

Carrier tape structure and Dimensions




(Unit: mm) **Dimensions List** C D E F G 1.75<sup>±0.1</sup> 16.0±0.3  $7.5^{\pm0.1}$ 8.0<sup>±0.1</sup>  $2.0^{\pm0.1}$  $4.0^{\pm0.1}$  $\phi 1.5^{+0.1}_{-0}$ Η K  $4.2^{\pm0.1}$  $10.4^{\pm0.1}$  $0.4^{\pm0.05}$  $5.1^{\pm0.1}$ 

#### Reel structure and Dimensions



Dimensio	ns List	(Unit: mm)		
a	b	с	d	
330	330 17.5 <sup>±1.5</sup>		13 <sup>±0.5</sup>	
e	f	g		
23±1.0	2.0 <sup>±0.5</sup>	2.0 <sup>±0.5</sup>		

#### Direction of product insertion



[Packing: 2 000pcs/reel]



#### **■** Important Notices

- · The circuit application examples in this publication are provided to explain representative applications of SHARP devices and are not intended to guarantee any circuit design or license any intellectual property rights. SHARP takes no responsibility for any problems related to any intellectual property right of a third party resulting from the use of SHARP's devices.
- · Contact SHARP in order to obtain the latest device specification sheets before using any SHARP device. SHARP reserves the right to make changes in the specifications, characteristics, data, materials, structure, and other contents described herein at any time without notice in order to improve design or reliability. Manufacturing locations are also subject to change without notice.
- · Observe the following points when using any devices in this publication. SHARP takes no responsibility for damage caused by improper use of the devices which does not meet the conditions and absolute maximum ratings to be used specified in the relevant specification sheet nor meet the following conditions:
- (i) The devices in this publication are designed for use in general electronic equipment designs such as:
  - --- Personal computers
  - --- Office automation equipment
  - --- Telecommunication equipment [terminal]
  - --- Test and measurement equipment
  - --- Industrial control
  - --- Audio visual equipment
  - --- Consumer electronics
- (ii) Measures such as fail-safe function and redundant design should be taken to ensure reliability and safety when SHARP devices are used for or in connection

with equipment that requires higher reliability such as:

- --- Transportation control and safety equipment (i.e., aircraft, trains, automobiles, etc.)
- --- Traffic signals
- --- Gas leakage sensor breakers
- --- Alarm equipment
- --- Various safety devices, etc.
- (iii) SHARP devices shall not be used for or in connection with equipment that requires an extremely high level of reliability and safety such as:
  - --- Space applications
  - --- Telecommunication equipment [trunk lines]
  - --- Nuclear power control equipment
  - --- Medical and other life support equipment (e.g., scuba).
- · If the SHARP devices listed in this publication fall within the scope of strategic products described in the Foreign Exchange and Foreign Trade Law of Japan, it is necessary to obtain approval to export such SHARP devices.
- This publication is the proprietary product of SHARP and is copyrighted, with all rights reserved. Under the copyright laws, no part of this publication may be reproduced or transmitted in any form or by any means, electronic or mechanical, for any purpose, in whole or in part, without the express written permission of SHARP. Express written permission is also required before any use of this publication may be made by a third party.
- · Contact and consult with a SHARP representative if there are any questions about the contents of this publication.